



Daves Big Brew

07070 707070

info@yourdevelopments

<https://davesbigbrew.co.uk>



Scan to view digital version

Daves Big Brew

Site Induction

Project: L-Shaped Single-Storey Extension

Site Address: 12 Example Street, Thistown, Thatcity, This County, DX2 3XB

Date: 30 March 2026

Site Rules

You must have a valid CSCS card to enter the site. Always wear a hard hat, high-visibility jacket, steel-toe boots, and safety gloves. You must sign in and out at the site office every day. There is a zero-tolerance policy for drugs and alcohol on site. Never use your mobile phone while working, and only use it in designated areas. Photography is strictly forbidden without permission. Smoking is only allowed in the designated smoking area. Keep the site tidy and clean up after yourself. Visitors must be accompanied by a site manager at all times. For this project, you must also adhere to the agreed working hours and respect the client's property.

Reporting Procedures

You must report all accidents, near misses, and unsafe conditions to the site manager immediately. Record all incidents in the accident book. Near-miss cards are available in the welfare unit. If you identify an unsafe condition, stop the job and inform the site manager right away.

Welfare Arrangements

There is a portacabin welfare unit on site where you can eat, make a brew, and use the toilet. Drinking water is available in the welfare unit. There is a drying room for wet clothes and boots. Hand washing facilities are provided in the welfare unit. Mr Whatyoucallit has agreed to allow us to use the kitchen sink for hand washing if needed, but only with prior permission.

First Aid

First Aid and eyewash Kit & accident book are located on the shelf in the large shed. There will always be at least one first aider on site

Nearest Hospital / A&E: Royal Infirmary, 999 NeeNaw Lane,

Fire Strategy & Emergency Procedures

You must ensure all fire extinguishers are clearly marked and located at the entrance of the site and near the welfare unit. If there's a fire, you must activate the electric bell alarm and evacuate immediately using the main entrance. If the site is near a school or hospital, you must tie into their existing fire alarm system. Always follow the evacuation route marked on the site plan.

Assembly Point: In the event of a fire sound the airhorn (shelf in shed) everyone should evacuate to to the end of the driveway & cross the road. Emergency services can be contacted on 999

Key Contacts

| Role | Contact |
|----------------------|---------------------------------|
| Client | Mr Whatyoucallit — 07070 707070 |
| Principal Designer | Andy Stihl — 09191 91991 |
| Principal Contractor | Daves Big Brew — 07070 707070 |
| Emergency Services | 999 |
| HSE | 0345 300 9923 |

Induction Confirmation

By signing off on this document, I confirm that I have received and understood the site induction for this project.

Hazardous Substances on This Site

Daves Big Brew | 07070 707070 | Generated 30 March 2026

Hazardous Substances on This Site

The following hazardous substances may be encountered on this site. All workers must be aware of the associated health risks and required control measures before commencing work.

| Silica Dust (Respirable Crystalline Silica) — Dust | |
|---|--|
| Health Effects | Silicosis (irreversible lung scarring), lung cancer (Group 1 carcinogen — IARC), COPD, kidney disease. |
| Control Measures | Water suppression or on-tool extraction. FFP3 RPE. No dry sweeping. HEPA vacuum. Health surveillance for regular exposure. |
| WEL Limit | 0.1 mg/m ³ (respirable) |

| PVA Adhesive — Chemical | |
|--------------------------------|--|
| Health Effects | Low toxicity. Mild skin and eye irritation. Not classified as hazardous under CLP. |
| Control Measures | Wash hands after use. Eye protection if risk of splashing. Good ventilation. |
| WEL Limit | No specific WEL |

| Wood Dust (Hardwood) — Dust | |
|------------------------------------|---|
| Health Effects | Nasal cancer (Group 1 carcinogen for hardwood dust), asthma, dermatitis, rhinitis. |
| Control Measures | On-tool extraction (LEV). RPE if extraction insufficient. No dry sweeping. Health surveillance. |
| WEL Limit | 3 mg/m ³ (inhalable) |

| Wood Dust (Softwood) — Dust | |
|------------------------------------|---|
| Health Effects | Asthma, rhinitis, dermatitis. Lower cancer risk than hardwood but still significant at high exposure. |
| Control Measures | On-tool extraction. RPE if extraction insufficient. Good ventilation. No dry sweeping. |
| WEL Limit | 5 mg/m ³ (inhalable) |